

F-8-84

Ca. 1850-1920

Centerville Survey District

Woodsboro, Maryland

Private

The Centerville Survey District is a linear community of 11 log and frame mid-19th century houses along the southwest side of Coppermine Road which were once centered on a primary school which existed from the 1850's to the early 20th century. Although most of the houses have modern artificial siding, the general form of two-story, three-bay houses is still apparent. Small settlements such as Centerville often developed around a single structure such as a school, church, store, tavern, or mill which later disappeared or changed its function with the village remaining mostly intact long afterward.

F-8-84
Centerville Survey District
Woodsboro
Frederick County

HISTORIC CONTEXT:

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Piedmont
(Harford, Baltimore, Carroll, Frederick, Howard, Montgomery
Counties, and Baltimore City)

Chronological/Development Periods:
Agricultural-Industrial Transition 1815-1870 A.D.
Industrial/Urban Dominance 1870-1930 A.D.

Historic Period Themes:
Architecture, Landscape Architecture, and Community Planning

Resource Type:

Category: Buildings

Historic Environment: Village

Historic Function(s) and Use(s):
Domestic/single dwelling/residence

Known Design Source: None

7.1 Description

The Centerville Survey District is a group of 10 dwelling houses and one archeological site located principally on the southwest side of Coppermine Road at the intersection of Whiskey Springs Road near Woodsboro, Frederick County, Maryland. The two-story houses are mostly mid to late 19th century in date and most have at least some log structure within later additions of frame and concrete block. The archeological site is the location of a public school which probably was built in the second quarter of the 19th century and was demolished in the first quarter of the 20th century.

The typical house in the Centerville Survey District is a two-story log central structure with a gable roof and a three-bay main elevation. One-story porches on the main facade are common to all the houses except the only house not on Coppermine Road, 11304 Whiskey Springs Road. Most of the porches have been altered, either by complete or partial enclosure. The entries are primarily in the center bay; only one house, 11403 Coppermine Road, has the double entry doors commonly found in German houses of the early and mid 19th century in Frederick County. Others of the type may exist in the survey district, but have been altered or concealed by enclosures. All houses have artificial siding of aluminum, vinyl corrugated metal, or composition shingle. Chimneys are interior, located at one or both gable ends of the houses. Roofs are mostly standing seam tin, with composition roofing on at least one house, 11411 Coppermine Road. Additions have been made to every house, usually extensions of the rear ell which was common to the basic plan. In some cases, these additions obscure the original plan and exterior, such as at 11305 Coppermine Road, which is set back about 50 yards from the road. Of all the contributing resources in the survey district, 11237 Coppermine Road is the best preserved example of the probably original form of the typical house.

Each dwelling house has small frame outbuildings, some of which may be of the same period as the main house but which have new exterior materials in whole or in part. The house at 11305 Coppermine has several large frame and metal animal sheds. Most properties include between 2 and 4 outbuildings.

Two non-contributing recently built houses, 11309 and 11405 Coppermine Road, are included within the survey district.

The archeological site is unverified by testing and is located on the district sketch map according to information from Mr. E.L. Long, owner of 11305 Coppermine Road.

8.1 Significance

The Centerville Survey District illustrates the settlement of small linear communities in the mid-19th century along roads near public schools, churches, stores, taverns, and other social, educational, religious, and economic activities. In this case, the probable magnet to development of the village was the school which stood near the junction of Coppermine and Whiskey Springs Road. The school (demolished in the early 20th century) is shown on the 1858 map with no houses or buildings other than neighboring farm houses nearby. By 1873 most of the houses now standing were built, although the village was not named on the C.O. Titus Atlas of Frederick County of that year. The houses have a low level of architectural significance because of alterations and exterior modern materials, but retain enough of their original form and detail to convey a sense of their mid to late 19th century origins.

The Centerville Survey District was compared to another small community in the Woodsboro Election District, Troutville, a group of 4 houses remaining from a larger village which developed around a mill, and Clemsonville, in the Johnsville Election District, where a former store and a dwelling house remain from a small crossroads village. These villages share several characteristics, one being the central activity which focused the community no longer surviving and another being the subsequent lack of growth and loss of some structures. As three such communities have been documented in two election districts, the assumption is that several more exist in other sections of the County. Their architectural significance is probably comparably low with the possibility of an exceptional structure surviving in communities not yet surveyed.

Maryland Historical Trust State Historic Sites Inventory Form

1. Name (indicate preferred name)

historic Centerville Survey District

and/or common

2. Location

street & number Southwest side of 11200-11400 block Coppermine Road not for publication

city, town Woodsboro X vicinity of congressional district 6th

state Maryland county Frederick

3. Classification

Category	Ownership	Status	Present Use
<u> </u> X district	<u> </u> public	<u> </u> X occupied	<u> </u> agriculture
<u> </u> building(s)	<u> </u> X private	<u> </u> unoccupied	<u> </u> commercial
<u> </u> structure	<u> </u> both	<u> </u> work in progress	<u> </u> educational
<u> </u> site	Public Acquisition	Accessible	<u> </u> entertainment
<u> </u> object	<u> </u> in process	<u> </u> X yes: restricted	<u> </u> government
	<u> </u> being considered	<u> </u> yes: unrestricted	<u> </u> industrial
	<u> </u> X not applicable	<u> </u> no	<u> </u> military
			<u> </u> museum
			<u> </u> park
			<u> </u> X private residence
			<u> </u> religious
			<u> </u> scientific
			<u> </u> transportation
			<u> </u> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Multiple owners

street & number telephone no.:

city, town state and zip code

5. Location of Legal Description

courthouse, registry of deeds, etc. Frederick County Courthouse liber

street & number 100 W. Patrick Street folio

city, town Frederick state Md.

6. Representation in Existing Historical Surveys

title

date federal state county local

pository for survey records

city, town state

7. Description

Survey No. F-8-84

Condition

☐ excellent

☒ good

☒ fair

☐ deteriorated

☐ ruins

☐ unexposed

Check one

☐ unaltered

☒ altered

Check one

☒ original site

☐ moved date of move

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Contributing Resource Count: 11

(Description on separate sheet)

8. Significance

Survey No. F-8-84

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input checked="" type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400–1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500–1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600–1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700–1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800–1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900–	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates Ca. 1850-1920 **Builder/Architect**

check: Applicable Criteria: ☒ A ☐ B ☒ C ☐ D
and/or

Applicable Exception: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Level of Significance: ☐ national ☐ state ☒ local

Prepare both a summary paragraph of significance and a general statement of history and support.

(Significance on separate sheet)

9. Major Bibliographical References

Survey No. F-8-84

Bond, Isaac, Map of Frederick County, 1858
Titus, C.O., Atlas of Frederick County, 1873

10. Geographical Data

Acreage of nominated property Woodsboro, Md.Quadrangle name Woodsboro, Md.Quadrangle scale 1:24000UTM References do NOT complete UTM references

A

--	--	--	--	--	--	--	--	--	--

Zone Easting Northing

B

--	--	--	--	--	--	--	--	--	--

Zone Easting Northing

C

--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification

As outlined on the attached USGS quad map

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------


11. Form Prepared By

name/title Janet L. Davis, Historic Sites Surveyororganization Frederick County Planning & Zoning date May, 1991street & number 12 E. Church Street telephone 696-2958city or town Frederick state Md. 21701


The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438





F-8-84
Centerville Survey
District
Frederick County
Resource Sketch
Map
Janet Davis
May 21, 1991



F-8-84
Centerville Survey District
Frederick County
Isaac Bond, Map of Frederick County, 1858

Scale $1\frac{1}{2}$ inches to the mile






F-8-84
Centerville Survey District
Frederick County
U.S.G.S. Woodsboro, Md. Quadrangle
1:24000

LIBERTYTOWN 1.8 MI. 30°00'00" E 77°00'00" E

ROAD CLASSIFICATION

Heavy-duty _____ 4 LANE 6 LANE Light-duty _____
Medium-duty _____ 4 LANE 6 LANE Unimproved dirt _____
U.S. Route State Route





F-8-84

Centerville Survey District

Frederick County

Photo: Mary Shipe

March 1991

Neg. loc.: Maryland Historical Trust
Annapolis, MD

11237 Coppermine Rd., east elevation

1/5



F. 8-84

Centerville Survey District

Frederick County

Photo: Mary Shipe

March 1991

Neg. loc.: Maryland Historical Trust
Annapolis, MD

11305 Coppermine Rd., general view from
Southeast

2/5



F-8-84

Centerville Survey District

Frederick County

Photo: Moty Shipe

March 1991

Neg. loc.: Maryland Historical Trust

Annapolis, MD

View southeast on Coppermine Road

3/5



F-8-84

Centerville Survey District

Frederick County

Photo: Mory Shipe

March 1991

Neg loc.: Maryland Historical Trust

Annapolis, MD

View northwest on Coppermine Road

4/5



F-8-84

Centerville Survey District

Frederick County

Photo: Mary Shipe

March 1991

Neg. loc.: Maryland Historical Trust

Annapolis, MD

11411 Coppermine Rd., east elevation

5/5